

# Rental Cooling Tower Package

# 79 Ton

## General System Data

Fully packaged unit, completely assembled, arrives on job site ready for installation in minimal time.

## Basic Equipment Data

Fluid Type	Water
Flow (GPM)	237 GPM
Entering Fluid Temp (F°)	95°
Leaving Fluid Temp (F°)	85°
Wet Bulb (F°)	78°
# Fans	1
Fan Motor Horsepower (1)	3 hp
Inlet Water Connection Size	4" Flanged
Outlet Water Connection Size	4" Flanged
Make-up Water Connection Size	3/4"
Overflow	(1) 2" dia. FPT/Man.
Chemical (Optional)	(1) 3/4" dia. FPT/Man.
Equipment Insurance Value	\$25,000.00

## Electrical Data

Nominal Voltage	460V / 60Hz / 3Ø
Fan Circuit	20 Amps
Basin Heater Circuit	20 Amps
Control Circuit	115/120 Volt

## Physical Data

Length	11 1/2'
Width	67"
Height	103"
Operating Weight	3,500 lbs.

## Equipment Features & Options

- Disconnect Switch
- Temperature Control
- Basin Heater

